

Partial Completion Schedule

Single Family Residential

		Percent of Total	Cumulative Percent of Total
1	Plans, permits and preliminary work.....	3	3
2	Forms and ground plumbing.....	4	7
3	Slab and footings.....	9	16
4	Framing.....	20	36
5	Windows and sliding glass doors.....	1	37
6	Roof covering.....	3	40
7	Plumbing - top out and sewer connections.....	4	44
8	Insulation.....	1	45
9	Wiring.....	4	49
10	Fireplace.....	3	52
11	Exterior stucco or siding.....	6	58
12	Interior drywall and spray plaster.....	8	66
13	Finish floors (including kitchen and bath).....	5	71
14	Doors, frames and weather stripping.....	3	74
15	Built-in cabinets, interior trim and finishes.....	9	83
16	Plumbing fixtures (including water heater).....	4	87
17	Built-in appliances and equipment.....	4	91
18	Light fixtures.....	1	92
19	Finish hardware.....	1	93
20	Painting and decorating.....	4	97
21	Exterior paving and flatwork.....	3	100